



IMI performed the mechanical work on the new pumping station at the airports north detention basin. The station is a wet/dry well arrangement, with (3) 3,500 GPM variable speed pumps and (2) 2,000 GPM low speed pumps. There is also (1) 1,800 gallon/2000 GPM oil/water separator. IMI installed all equipment and piping associated with the project.

Owner
City of Chicago, Dept. of Aviation

Client
Walsh Construction

Location
O'Hare Airport

Architect
CTE/AECOM

IMI contract amount
\$827,000

Completion
January 2009

